

LAS COLINAS BLVD

This project is for the improvement of Las Colinas Blvd from Riverside Dr to Fuller Dr. The project has been broken into phases to facilitate funding. The portion from just south of Wingren to Fuller (Phase 1 and 2) was completed in April, 2019.

Phase 3 will be from Lake Carolyn Parkway north to the end of the just completed construction.

This project includes: 22,983 SY of concrete flatwork removal; 18,474 SY of 10.50" reinforced concrete pavement; 1,264 SY of 8" reinforced concrete pavement; 3,969 SY of 5" reinforced concrete sidewalk; 1,452 LF of 18" thru 30" RCP storm sewer; 634 LF of 8" wastewater main and 2,554 LF of 6" thru 16" water main.

Contractor: Tiseo Paving Company

Notice to Proceed: 10/07/2019

Contract: \$7,446,002.90

Project Time: 365 Calendar Days

This product is for informational purposes and may not have been prepared for or be suitable for legal, engineering or surveying purposes. It does not represent an on-the-ground survey and represents only the approximate relative location of property boundaries.

